

Exteriors, T. 2 S., R. 35 E., W.M.

Chains		Feet
	N. bet. Secs. 7 & 12.	
	Var. 17° 30' E.	
	Descend through dense forests of pine undergrowth and fallen timber.	
10.00	A spring branch at bottom of canyon, course N.W.	
13.00	Point of ridge, course N.E. Descend through dense fir thicket.	
16.00	Bottom of canyon, course S.W. Water course dry.	
25.15	A scrubby pine, 20 ins. diam. on ledge of rock- a lone tree.	
30.50	Enter heavy open timber.	
40.00	Set post, 3 ft. long, 3 ins. sq., 18 ins. in ground, on summit of mountain, in open timber, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on E. & W. faces, from which,	
	Var. 19° E.	
	A pine, 30 ins. diam., brs. N. 54° W., 46 lks; dist., marked $\frac{1}{4}$ S., B.T.	
	A pine, 4 ins. diam., brs. S. 64° E., 62 lks. dist., marked $\frac{1}{4}$ S., B.T.	
	Descend through heavy timber.	
80.00	Set post, 4 $\frac{1}{2}$ ft. long, 4 ins. sq., 24 ins. in ground, on table land, in heavy pine timber, for Cor. to Secs. 1, 7, 6 & 12, marked,	
	T. 2 S., S. 6 on N.E.	
	R. 35 E., S. 7 on S.E.	
	R. 34 E., S. 12 on S.W. and	
	S. 1 on N.W. faces, with	
	5 notches on S. and	
	1 notch on N. edges, from which,	
	A pine, 30 ins. diam., brs. N. 54° W., 44 lks. dist., marked T. 2 S., R. 34 E., S. 1, B.T.	
	A pine, 20 ins. diam., brs. S. 25° W., 44 lks. dist., marked T. 2 S., R. 34 E., S. 12, B.T.	
	A pine, 36 ins. diam., brs. S. 28° E., 186 lks. dist., marked T. 2 S., R. 35 E., S. 7, B.T.	
	No other tree in limits & raised mound of stone alongside.	
	Land; mountain table land, with occasional ravines.	
	Soil; rocky 3rd rate. Timber; fir, pine & tamarack.	