

## Subdivisional Lines, T. 2 S., R. 34 E., W.M.

Chains		Feet
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which, A fir, 16 ins. diam., brs. S.70°E., 25 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 18 ins. diam., brs. N.25°W., 40 lks. dist., marked $\frac{1}{4}$ S., B.T.	
46.75	Daly Wagon Road, N.W.	
79.50	Gulch, course N.E.	
80.00	Set basalt stone, 10 x 10 x 12 ins., 8 ins. in ground, for Cor. to Secs. 25, 26, 35 & 36, marked with 7 notches on S. & E. edges. Raised mound of stone alongside, Pits impracticable.	
Land; mountainous and brushy, 43.55 chs.		
Some pine & fir timber. Good grass. Soil; 3rd rate.		
E. on true line bet. Secs. 25 & 36.		
Var. 19° E.		
1.00	Gulch or canyon, N.E.	-50
6.00	Top of ridge, N.	+100
13.00	Branch, 5 lks. wide, N.W.	-100
Ascend.		
15.85	Intersect U.R. Bdy., 5.60 chs., N.20°E. of Cor. to 62nd mile and	
Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Closing Cor. to Secs. 25 & 36, marked T.2 S., R.34 E., U.R., C.C. on W., Sec. 25 on N., & Sec. 36 on S. faces, from which,		
A pine, 8 ins. diam., brs. N.40°E., 27 lks. dist., marked T.2 S., U.R., C.C., S.25, B.T.		
A pine, 16 ins. diam., brs. S.25°W., 3 lks. dist., marked R.34 E., U.R., C.C., S.36, B.T.		
Land; rough and mountainous, 15.85 chs.		
Heavy pine & fir timber, 15.85 chs. Good bunch grass.		
Soil; rocky 2nd rate.		
N. bet. Secs. 25 & 26.		
Var. 19° E.		