

Subdivisional Lines, T. 2 S., R. 34 E., W.M.

Chains		Feet
40.00	Top of rimrock, 10 ft. high, which, I marked $\frac{1}{4}$ S. on N. face, with a cross (X) at exact Cor. point, $\frac{1}{4}$ Sec. Cor., over which, I raised mound of stone, 18 ins. high & $3\frac{1}{2}$ ft. base.	
41.00	Cross head of sharp deep canyon, course N.W.	
45.50	Intersect U.R.Bdy. at point, N.20°E. of 61st mile Cor., 10.75 chs. dist. Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for U.R. Closing Cor. to Secs. 24 & 25, marked T. 2 S., R. 34 E., U.R., C.C. on W. face S. 25 on N. and S. 24 on S. faces, from which, A pine, 12 ins. diam., brs. S. 30° E., 26 lks. dist., marked U.R., C.C., S. 24, B.T. A pine, 24 ins. diam., brs. N. 30° W., 26 lks. dist., marked U.R., C.C., S. 25, B.T. Land; rough and mountainous, 45.50 chs. Pine & fir timber. Good grass. Soil; 2nd rate.	
	W. on true line bet. Secs. 26 & 35. Var. 19° E.	
12.80	Top of mountain.	
33.00	Begin to descend.	
40.00	Set basalt stone, 12 x 12 x 24 ins., 18 ins. in ground, marked $\frac{1}{4}$ S. on N. face, for $\frac{1}{4}$ Sec. Cor., from which, A pine, 16 ins. diam., brs. N. 75° E., 34 lks. dist., marked $\frac{1}{4}$ S., B.T. A pine, 12 ins. diam., brs. S. 65° E., 34 lks. dist., marked $\frac{1}{4}$ S., B.T.	
60.60	Daly Wagon Road, N.W.	
76.50	Ravine, N.W.	
80.00	Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for Cor. to Secs. 26, 27, 34 & 35, marked T. 2 S., R. 34 E., S. 26 on N.E. R. 34 E., S. 35 on S.E.	