

Subdivisional Lines, T.2 S., R.34 E., W.M.

Chains

Feet

S.34 on S.W. and

S.27 on N.W. faces, from which,

A pine, 16 ins. diam., brs. N.62°E., 76 lks. dist.,
marked T.2 S., R.34 E., S.26, B.T.

A pine, 8 ins. diam., brs. S.25°E., 46 lks. dist.,
marked T.2 S., R.34 E., S.35, B.T.

A pine, 6 ins. diam., brs. S.25°W., 70 lks. dist.,
marked T.2 S., R.34 E., S.34, B.T.

A pine, 10 ins. diam., brs. N.48°W., 59 lks. dist.,
marked T.2 S., R.34 E., S.27, B.T.

Land; rolling. Scattering pine, fir and tamarack timber.
Soil; 2nd rate & rocky.

S. on true line bet. Secs. 34 & 35.

Var. 19°E.

17.00 Summit of ridge & bluff of rock, 10 ft. high.

40.00 Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$
Sec. Cor., marked $\frac{1}{4}$ S. on W. face, from which,

A pine, 24 ins. diam., brs. N.20°E., 104 lks. dist.,
marked $\frac{1}{4}$ S., B.T.

A pine, 24 ins. diam., brs. S.70°E., 73 lks. dist.,
marked $\frac{1}{4}$ S., B.T.

50.00 Intersect U.R. Bdy., 5.25 chs. W. of $\frac{1}{2}$ mile Cor. in 64th
mile and

Set post, 4 ft. long, 4 ins. sq., 24 ins. in ground, for
U.R. Closing Cor. to Secs. 34 & 35, marked

T.2 S., R.34 E., U.R., C.C. on N.,

S.35 on E. and

S.34 on W. faces, from which,

A black pine, 10 ins. diam., brs. N.85°E., 62 lks. dist.,
marked U.R., C.C., S.35, B.T.

A fir, 6 ins. diam., brs. S.75°W., 25 lks. dist.,
marked U.R., C.C., S.34, B.T.

Land; mostly level. Scattering pine timber. Soil; 2nd rate.