

## Subdivisional Lines, T.2 S., R.34 E., W.M.

Chains		Feet
	N. on true line bet. Secs. 16 & 17. Var. 18°30'E.	
2.00	Descend & enter timber.	
15.00	Leave timber.	
40.00	Set basalt stone, 7 x 9 x 12 ins., 8 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on W. face, over which, I raised mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base. Pits impracticable.	
80.00	Set basalt stone, 10 x 10 x 12 ins., 8 ins. in ground, for Cor. to Secs. 8, 9, 16 & 16, marked with 4 notches on S. & E. edges, over which, I raised mound of stone, 2 ft. high with $4\frac{1}{2}$ ft. base. Pits impracticable. Land; mostly level. Open pine timber. Bunch grass good. Soil; rocky and 4th rate.	
	E. on random bet. Secs. 9 & 16. Var. 20°E.	
40.00	Set temp. $\frac{1}{4}$ Sec. Cor.	
80.00	Intersect N. & S. line at Cor. to Secs. 9, 10, 15 & 16. Thence W. on true line Var. 18°E.	
	Ascend.	
10.00	Top of ridge, N.	+600
40.00	Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ S. on N. face, from which, A fir, 12 ins. diam., brs. N.20°E., 16 lks. dist., marked $\frac{1}{4}$ S., B.T. A fir, 14 ins. diam., brs. S.89°W., 25 lks. dist., marked $\frac{1}{4}$ S., B.T.	
47.25	Rattle Snake Canyon	400
80.00	To Cor. to Secs. 8, 9, 16 & 17. Land; rough and mountainous, 80 chs. Brushy pine & fir timber. Some underbrush. Soil; rocky and 2nd rate.	