

## Subdivisional Lines, T.2 S., R.34 E., W. M.

Chains		Feet
65.00	Canyon, N.	-600
76.00	Top of ridge, N.	†200
79.60	To Cor. to Secs. 7, 8, 17 & 18. Land; mountainous, 79.60 chs. Some bunch grass. Soil; 4th rate and rocky.	
W. on true line bet. Secs. 7 & 18. Var. 20° E.		
4.00	Point of high rock, N.	† 80
18.65	Bed of Creek, water in holes.	-700
40.00	Set basalt stone, 12 x 12 x 16 ins., 10 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on N. face, over which, I erected mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.	†800
56.25	Gulch, S.	-200
79.00	Intersect Tp. line, 4.00 chs. N. of Cor. to Secs. 12 & 13, T.2 S., R.33 E. and Set stone, 12 x 18 x 18 ins., 12 ins. in ground, for Clos- ing Cor. to Secs. 7 & 18, marked U.R., C.C. on E. face, with 4 notches on S. and 2 on N. edges, over which, I raised mound of stone, 2 ft. high with $4\frac{1}{2}$ Ft. base. Land; mountainous, 79 chs. Soil; 3rd rate. Timber; in canyons, accessible only at head of canyons. Some bunch grass.	
N. on true line bet. Secs. 7 & 8. Var. 20° E.		
27.00	Canyon, N.E.	-500
40.00	Set stone, 10 x 12 x 20 ins., 14 ins. in ground, for $\frac{1}{4}$ Sec. Cor., marked $\frac{1}{4}$ on W. face, around which, I raised mound of stone, 18 ins. high with $3\frac{1}{2}$ ft. base.	†300
44.55	Gulch, E.	-200
63.15	" "	- 75
68.00	Summit of ridge or point, E.	† 400