

## Resurvey portion E. Bdy., T.2 S., R.34 E., W.M.

Chains	Feet
	<p>ground, for <math>\frac{1}{4}</math> Sec. Cor., with brass cap, marked</p> <p style="text-align: center;"> <math>\frac{1}{4}</math>            S13   S18            1917         </p> <p>from which,</p> <p>A fir, 15 ins. diam., brs. N.45°45'W., 18 lks. dist., marked <math>\frac{1}{4}</math> S (lower blaze healed over).</p> <p>A pine, 48 ins. diam., brs. N.44°20'E., 70 lks. dist., marked <math>\frac{1}{4}</math> S., B.T.</p> <p>Thence North, continuing my measurements.</p>
80.40	<p>Intersect the old Cor. of Secs. 7, 12, 13 &amp; 18, which is a badly decayed post, 4 x 4 x 36 ins., above ground, witnessed as described by the surveyor general. At the exact Cor. point</p> <p>Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in the ground, for Cor. to Secs. 7, 12, 13 &amp; 18, with brass cap marked,</p> <p style="text-align: center;">           T2S            R34E   R35E            S12   S7            S13   S18            1917         </p> <p>from which,</p> <p>A dead fir, 16 ins. diam., brs. N.50°E., 40 lks. dist., marks illegible (Old B.T.)</p> <p>A dead fir, 12 ins. diam., brs. S.34°E., 31 lks. dist., marked T.2 S., R.35E., S.18, B.T. (Old B.T.)</p> <p>A fir, 12 ins. diam., brs. S.12°W., 19 lks. dist., marked T.2 S., R.34 E., S.13, B.T. (Old B.T.)</p> <p>A fir, 16 ins. diam., brs. N.17°30'W., 72 lks. dist., marked T.2 S., R.34 E., S.12, B.T. (Old B.T.)</p> <p>A fir, 10 ins. diam., brs. N.34°E., 77 lks. dist., marked T.2 S., R.35E., S.7, B.T. (New B.T.)</p> <p>A fir, 24 ins. diam., brs. S.87°E., 52 lks. dist., marked T.2 S., R.35E., S.18, B.T. (New B.T.)</p> <p>A fir, 5 ins. diam., brs. N.32°W., 36 lks. dist., marked T.2 S., R.34 E., S.12, B.T. (New B.T.)</p> <p>Land; rolling, bench and mountainous.</p> <p>Soil; light loam on basalt rock, 2nd rate.</p>