

Resurvey portion E. Bdy., T.2 S., R.34 E., W. M.

Chains

Feet.

marked T.1 S., R.35 E., S.31, B.T. (Old B.T.)

A fir, 12 ins. diam., brs. S.17°45'W., 352 lks. dist.,

marked T.2 S., R.34 E., S.1, B.T. (New B.T.)

Land; mountainous, bench & rolling.

Soil; light, shallow loam, on basalt bedrock, 2nd rate.

Timber; yellow pine, balsam, fir and tamarack.

Undergrowth; balsam, lodgepole pine & willow.

Retracement- Resurvey of Subdivisional Lines, T.2S., R.34 E.  
As surveyed by same U.S. Deputy Surveyor,  
Under same Group & Instructions.

I commence at the Cor. of Secs. 23, 24, 25 & 26, the position of which is determined by reference to the original bearing trees. At the exact corner point

Set an iron post, 3 ft. long, 2 ins. diam., 24 ins. in ground, for Cor. to Secs. 23, 24, 25 & 26, with brass cap, marked,

T2S	R34E
S23	S24
S26	S25
1917	

from which,

A pine, 24 ins. diam., brs. N.20°W., 117 lks. dist.,  
marked in the bark, marks illegible. I remark it  
T.2 S., R.34 E., S.23, B.T. (Old B.T.)

A pine, 8 ins. diam., brs. S.47°W., 133 lks. dist.,  
blazes healed over, not opened (Old B.T.)

A fir stump, 24 ins. diam., brs. N.83/4°E., 234 lks.  
dist., marked in the mark, illegible (Old B.T.)

A fir, 30 ins. diam., brs. N.42°E., 183 lks. dist.,  
marked T.2 S., R.34 E., S.24, B.T. (New B.T.)

A pine, 12 ins. diam., brs. S.70°E., 445 lks. dist.,  
marked T.2 S., R.34 E., S.25, B.T. (New B.T.)

Lat. 45° 23' N., Long. 118° 29' W., Mean Mag. Decl. 19° 30' E.

Thence

East, retracing bet. Secs. 24 & 25.

40.03

Fall 23 lks. S. of 1/4 Sec. Cor. I find no evidence of the  
Cor., except the rimrock, 5 ft. high, 15 lks. E. & W.