

Resurvey, Subdivisional Lines, T.2 S., R.34 E., W. M.

| Chains | | Feet |
|--------|--|------|
| | <p>which is unmistakable, on top of which I cut a cross (X) and $\frac{1}{4}$ on N. face; from which,</p> <p>A pine, 12 ins. diam., brs. S.23°E., 100 lks. dist., marked $\frac{1}{4}$ S.25, B.T.</p> <p>A pine, 24 ins. diam., brs. N.60°E., 175 lks. dist., marked $\frac{1}{4}$ S.24, B.T.</p> <p>The true course and distance of this line to the $\frac{1}{4}$ Sec. Cor. is N.89°40'E., 40.03 chs.</p> <p>A flag on the old Closing Cor. of Secs. 24 & 25, being plainly visible, I run for said Cor. N.89°20'E., on a true line, counting distance from the Sec. Cor.</p> | |
| 46.31 | <p>Intersect the old Closing Cor. of Secs. 24 & 25, which is a post, 3 x 3 x 30 ins., set in small mound of stone, marked C.C. on N. and U.R. on S. faces; from which,</p> <p>A pine, 30 ins. diam., brs. North, 26 lks. dist., marked C.C., U.R., B.T.</p> <p>A fir, 15 ins. diam., brs. S.36°E., 27 lks. dist., marked C.C., U.R., B.T.</p> | |
| 46.76 | <p>Intersect true E. Bdy. of original Umatilla Indian Reservation, 12.89 chs., N.19°14'E. from the 61 Mile Cor.</p> <p>At the point of intersection</p> <p>Set an iron post, 3 ft. long, 2 ins. diam., 6 ins. in ground surrounded by mound of stone, 4 ft. base, 2 ft. high, for Closing Cor. of Secs. 24 & 25, with brass cap, marked,</p> <div style="text-align: center; margin: 10px 0;"> $\begin{array}{r} \text{T2SR34E} \\ \text{CC} \quad \frac{\text{S24}}{\text{S25}} \\ \hline 1917 \end{array}$ </div> <p>from which,</p> <p>A fir, 15 ins. diam., brs. S.50°W., 37 lks. dist., marked C.C., U.R., T.2 S., R.34 E., S.25, B.T.</p> <p>A pine, 30 ins. diam., brs. N.60°W., 51 lks. dist., marked C.C., U.R., T.2 S., R.34 E., S.24, B.T.</p> <p>Land; mountainous.</p> <p>Soil; rocky, 3rd rate.</p> <p>Timber; pine & fir. Undergrowth; pine.</p> | |