

Re-survey Subdivisional Lines, T.2 S., R.34 E., W.M.

Chains		Feet
	From the Cor. of Secs. 23, 24, 25 & 26. N.0°13'E., bet. Secs. 23 & 24. Over mountainous land, through heavy timber & dense under- growth. Along steep broken W. slope.	
12.90	Top of spur, slopes N.W.; descend 414 ft. to	
22.46	Dry gulch, course N.80°W., ascend 75 ft. to	
28.755	Top of spur, slopes N.80°W.; descend 365 ft. to	
40.00	Set iron post, 3 ft. long, 1 in. diam., 26 ins. in ground, for $\frac{1}{4}$ Sec. Cor., with brass cap, marked, <div style="text-align: center;"> $\frac{1}{4}$ S23 S24 1917 </div> from which, A lodgepole pine, 6 ins. diam., brs. S.75°E., 3 lks. dist., marked $\frac{1}{4}$ S.24, B.T. A fir, 5 ins. diam., brs. S.70°W., 23 lks. dist., marked $\frac{1}{4}$ S.23, B.T. Descend 60 ft. to	
41.40	Branch of Johnson Creek, 10 lks. wide, course W., ascend 200 290 ft. to	
48.50	Top of spur, slopes W., descend 200 ft. to	
63.70	Bear Creek, 10 lks. wide, course S.70°W., no water at crossing. Ascend 615 ft. to	
80.00	Set iron post, 3 ft. long, 2 ins. diam., 16 ins. in ground surrounded by mound of stone, 4 ft. base, $1\frac{1}{2}$ ft. high, for Cor. of Secs. 13, 14, 23 & 24, with brass cap, marked, <div style="text-align: center;"> T28 R4E S14 S13 S23 S24 1917 </div> from which, A pine, 18 ins. diam., brs. N.70°E., 117 lks. dist., marked T.2 S., R.34 E., S.13, B.T. A pine, 14 ins. diam., brs. S.47°30'W., 39 lks. dist., marked T.2 S., R.34 E., S.23, B.T. A pine, 16 ins. diam., brs. N.39°30'W., 42 lks. dist., marked T.2 S., R.34 E., S.14, B.T.	