

## Retracement Portion Subdivisional Lines, T.2 S., R.34 E., W.M.

Chains		Feet
5.94	<p>W., bet. Secs. 13 &amp; 24.</p> <p>Over rolling land, through timber &amp; undergrowth.</p> <p>Intersect E.Bdy. of original Indian Reservation, at Closing Cor. of that portion of Secs. 13 &amp; 24, within the Umatilla Reservation, which is an iron post, firmly set, marked &amp; witnessed as described by the Surveyor-General.</p> <p>I change the markings on the brass cap to read as follows;</p> <div style="text-align: center;"> <p>T2S R34E  <del>S13</del> / S13  CC <del>S24</del> / S24 CC  1917</p> </div> <p>and mark new bearing trees as follows;</p> <p>A fir, 12 ins. diam., brs. N.77°E., 59 lks. dist., marked C.C., T.2 S., R.34 E., S.13, B.T.</p> <p>A pine, 20 ins. diam., brs. S.59°30'W., 54 lks. dist., marked C.C., T.2 S., R.34 E., U.I.R., B.T.</p> <p>Land; rolling.</p> <p>Soil; light, scant loam, 2hd rate.</p> <p>Timber; pine &amp; fir.</p> <p>Undergrowth; fir, pine &amp; serviceberry.</p>	
29.82	<p>Commence at Cor. of Secs. 2, 3, 34 &amp; 35, on S. Bdy. of Tp., which is volcanic stone, 12 x 8 x 12 ins., above ground, firmly set, marked with 2 notches on E. &amp; 4 notches on W. edge, from which,</p> <p>A pine, 36 ins. diam., brs. N.72°E., 142 lks. dist., marked T.2 S., R.34 E., S.35, B.T.</p> <p>A pine, 16 ins. diam., brs. S.38°E., 161 lks. dist., marked T.3 S., R.34 E., S.2, B.T.</p> <p>A tamarack, 28 ins. diam., brs. S.81°30'W., 85 lks. dist., marked T.3 S., R.34 E., S.3, B.T.</p> <p>A tamarack, 28 ins. diam., brs. N.64°W., 100 lks. dist., marked T.2 S., R.34 E., S.34, B.T.</p> <p>Thence</p> <p>N. bet. Secs. 34 &amp; 35.</p> <p>Over rolling bench land, through heavy timber.</p> <p>Intersect S. Bdy. of original Umatilla Indian Reservation, N.89°49'W., 4.76 chs. from 63½ Mile Cor.</p>	29.62