

Retracement Portion Subdivisional Lines, T.2 S., R.34 E., W.M.

Chains		Feet				
	<p>from which,</p> <p>A pine, 6 ins. diam., brs. S. 62°45'E., 167 lks. dist., marked C.C., T.2 S., R.34 E., S.34, B.T.</p> <p>A pine, 8 ins. diam., brs. S. 56°30'W., 234 lks. dist., marked C.C., T.2 S., R.34 E., S.33, B.T.</p> <p>The Closing Cor. of that portion of Secs. 33 & 34, within original Umatill Indian Reservation, brs. N. 89°27'W., 110 lks. dist.</p> <p>Land; mountainous.</p> <p>Soil; light shallow loam, 3rd rate.</p> <p>Timber; yellow & lodgepole pine.</p> <p>Undergrowth; none.</p>					
	<p>From the Cor. of Secs. 32 & 33, on S. Bdy. of Tp., previously described,</p> <p>N., bet. Secs. 32 & 33</p> <p>Over bench; through heavy timber & medium undergrowth.</p>					
31:20	Intersect Old Closing Cor. of Secs. 32 & 33, which is a tamarack tree, 8 ins. diam., marked & witnessed as described by the Surveyor-General.					
31:29	Intersect S. Bdy. of original Umatilla Indian Reservation at new Closing Cor. of that portion of Secs. 32 & 33, within original reservation, which is a 2 in. iron post, firmly set in ground, marked & witnessed as described by the Surveyor-General. I change the markings on the brass cap to read,					
	<div style="text-align: center;"> <p>C C</p> <p>T2S R34E</p> <p>UIR</p> <table border="1" style="margin: auto;"> <tr> <td>S32</td> <td>S33</td> </tr> <tr> <td>S32</td> <td>S33</td> </tr> </table> <p>C C</p> <p>1917</p> </div> <p>Land; high rolling bench.</p> <p>Soil; shallow light loam, 2nd & 3rd rate.</p> <p>Timber; yellow pine, tamarack & lodgepole pine.</p> <p>Undergrowth; balsam, honey laurel, willow & lodgepole pine.</p>	S32	S33	S32	S33	
S32	S33					
S32	S33					
	From the Cor. of Secs. 31 & 32, on S. Bdy. of Tp., previously described,					