

## Subdivisional Lines, T.3 N., R.27 E., W.M.

Chains		Feet
	deposited 1 pt. charcoal, as per instructions.	
46.00	Road from the Dalles to Walla Walla, brs. N.-N.E. Leave bottom & ascend high ground.	
79.90	The Cor. to Secs. 35, 36, 25 & 26. Soil; on bottom 1st rate, remainder, 2nd rate. Land; principally level. Frazer's pre-emption claim embraces the S.E. $\frac{1}{4}$ of Sec. 25.	
	<hr/>	
	N. bet. Secs. 25 & 26.	
40.00	Set post for Cor. Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 23, 24, 25 & 26, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; sandy, 3rd rate. Land; rolling.	
	<hr/>	
	E. on random line bet. Secs. 24 & 25. Var. 19°48'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.40	Intersect E. Bdy. of Tp., 17 lks. S. of Cor. to Secs. 24, 25, 19 & <sup>30</sup> 34, from which Cor., I run S.89°53'W. on true line bet. Secs. 24 & 25.	
40.20	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.40	The Cor. to Secs. 23, 25, 24 & 26. Soil; sandy, 3rd rate. Land; rolling.	
	<hr/>	
	N. bet. Secs. 23 & 24.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 13, 13, 23 & 24, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; sandy 3rd rate. Land; rolling.	