

Subdivisional Lines, T.3 N., R.27 E., W. M.

Chains	Feet
80.00	Set post, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions, for Cor. to Secs. 1, 2, 11 & 12. Land; level. Soil; sandy, 3rd rate. Vegetation scarce.
<hr/> E. on random line bet. Secs. 1 & 12.	
Var. 20° E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.50	Intersect E. Bdy. of Tp., 59 lks. S. of Cor. to Secs. 1, 12, 6 & 7, from which Cor., I run S. 89° 35' W. on true line bet. Secs. 1 & 12.
40.25	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits & deposited 1 pt. charcoal, as per instructions.
80.50	The Cor. to Secs. 1, 2, 11 & 13. Soil; sandy, 3rd rate. Land; rolling.
<hr/> N. on random line bet. Secs. 1 & 2.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.
80.25	Intersect N. Bdy. of Tp., 46 lks. W. of Cor. to Secs. 1, 2, 35 & 36, from which Cor., I run S. 0° 20' W. on true line bet. Secs. 1 & 2.
40.25	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits, & deposited 1 pt. charcoal, as per instructions.
80.25	The Cor. to Secs. 1, 2, 11 & 12. Land; level. Soil; sandy, 3rd rate.
Oct. 12, 1860.	
<hr/> N. bet. Secs. 34 & 35. Oct. 13, 1860.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.
80.00	Set post for Cor. to Secs. 34, 35, 26 & 27, in mound, with trench & pits. Deposited 1 pt. charcoal, as per instructions. Land; high & rolling.