

Subdivisional Lines, T. 3 N., T. 27 E., W. M.

Chains	Feet
80.00	Set post for Cor. to Secs. 14, 15, 22 & 23, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions. Soil; sandy, 3rd rate, sterile. Land; rolling and level.
<hr/> E. on random line bet. Secs. 14 & 23. <div style="text-align: right;">Var. 19°35'E.</div>	
40.00	Set post for temp. $\frac{1}{2}$ Sec. Cor.
79.82	Intersect N. & S. line, 49 lks. S. of Cor. to Secs. 13, 14, 23 & 24, from which Cor., I run S. 89°39' W. on true line bet. Secs. 14 & 23.
39.91	Set post for $\frac{1}{2}$ Sec. Cor., in mound; with trench & pits; deposited 1 pt. charcoal, as per instructions.
79.82	The Cor. to Secs. 14, 15, 22 & 23. Soil; sandy & sterile. Land; broken.
<hr/> N. bet. Secs. 14 & 15.	
40.00	Set post for $\frac{1}{2}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.
80.00	Set post for Cor. to Secs. 10, 11, 14 & 15, in mound, with trench & pits. Deposited 1 pt. charcoal, as per instructions. Soil; sandy & barren, producing prickly pear & some grass. Land; level.
<hr/> E. on random line bet. Secs. 11 & 14. <div style="text-align: right;">Var. 20°E.</div>	
40.00	Set post for temp. $\frac{1}{2}$ Sec. Cor.
79.87	Intersect N. & S. line, 10 lks. S. of Cor. to Secs. 11, 12, 13 & 14, from which Cor., I run S. 89°56' W. on true line bet. Secs. 11 & 14.
39.93 $\frac{1}{2}$	Set post for $\frac{1}{2}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.
79.87	The Cor. to Secs. 10, 11, 14 & 15.