

## Subdivisional Lines, T.3 N., R.27 E., W. M.

Chains	Oct.14, 1860.	Feet
	N. bet. Secs. 33 & 34.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 33, 34, 27 & 28, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
	Soil; 3rd rate, sandy.	
	Land; rolling.	
<hr/>		
	E. on random line bet. Secs. 27 & 34.	
	Var.19°45'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.30	Intersect N. & S. line, 15 lks. N. of Cor. to Secs. 26, 27, 34 & 35, from which Cor., I run N.89°54'W. on true line bet. Secs. 27 & 34.	
40.15	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits, & deposited 1 pt. charcoal, as per instructions.	
80.30	The Cor. to Secs. 27, 28, 33 & 34.	
	Soil; 3rd rate, producing grass.	
	Land; rolling.	
<hr/>		
	N. bet. Secs. 27 & 28.	
40.00	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
80.00	Set post for Cor. to Secs. 21, 22, 27 & 28, in mound, with trench & pits; deposited 1 pt. charcoal, as per instructions.	
	Soil; 3rd rate, sandy.	
	Land; rolling.	
<hr/>		
	E. on random line bet. Secs. 22 & 27. Var. 19°25'E.	
40.00	Set post for temp. $\frac{1}{4}$ Sec. Cor.	
80.24	Intersect N. & S. line, 35 lks. S. of Cor. to Secs. 22, 23, 26 & 27, from which Cor., I run S.89°45'W. on true line bet. Secs. 22 & 27.	
40.12	Set post for $\frac{1}{4}$ Sec. Cor., in mound, with trench & pits;	