

Subdivisions T. 3, N. R. 28 E.

Chains	
	N. 89° 30' West on true line between Secs. 25 & 36.
40.00	Set post for 1/4 Sec. corner in mound of earth.
41.25	Trail bears N. & S.
80.00	Intersect the corner to Secs. 25, 26, 35 & 36 in mound of earth.
	Land, level.
	Soil, 1st rate.
<hr/>	
	North between Secs. 25 & 26.
	Variation 19° 25' East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 23, 24, 25 & 26 in mound of earth &c., as per instructions.
	Land, level.
	Soil, 1st rate.
<hr/>	
	East on a random line between Sections 24 & 25.
40.00	Set post for temp. 1/4 Sec. corner.
80.07	Intersect East boundary 74 links North of Section corner.
	N. 89° 28' W. on true line between Sections 24 and 25.
7.00	Trail bears N. E. & S. W.
40.03	Set post for 1/4 Sec. corner in mound of earth &c as per instructions.
80.07	The corner to Secs. 23, 24, 25 & 26 in mound of earth &c., as per instructions.
	Land, level.
	Soil, 1st rate.
<hr/>	