

Subdivisions T. 3, N. R. 28 E.

Chains

North between Secs. 23 & 24.

Variation 20° East.

- 32.00 Emigrant Road bears E & W.
 - 40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
 - 80.00 Set post for corner to Secs. 13, 14, 23 & 24 in mound of earth &c., as per instructions.
- Land, gently rolling.
Soil, 2nd rate.

East on random line between Secs. 13 & 24.

- 40.00 Set post for temp. 1/4 Sec. corner.
 - 79.97 Intersect N & S Line 70 links North of Sec. corner.
N. 89° 30' W. on true line between Secs. 13 & 24.
 - 39.98 Set post for 1/4 Sec. corner in mound of earth.
 - 79.97 The corner to Secs. 13, 14, 23 & 24 in mound of earth &c.
- Land, level.
Soil, 1st rate.

North between Secs. 13 & 14.

Variation 20° East.

- 40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
 - 80.00 Set post for corner to Secs. 11, 12, 13 & 14 in mound of earth &c., as per instructions.
- Land, level.
Soil, very sandy.

East on random line between Secs. 12 & 13.

- 40.00 Set post for temp. 1/4 Sec. corner.
- 80.07 Intersect East boundary 80 links North of Sec. corner.
N. 89° 26' W. on true line between Secs. 12 & 13.
- 40.03 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
- 80.07 The corner to Secs. 11, 12, 13 & 14 in mound of earth.