

## Subdivisions T. 3, N.R. 28 E.

Chains	
	<p>Land, level.</p> <p>Soil, 2nd rate, very sandy.</p> <p style="text-align: right;">Sept. 22nd, 1859.</p>
	<p>North between Secs. 11 &amp; 12.</p> <p style="text-align: right;">Variation 20° 05' East.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 1, 2, 11 & 12 in mound of earth &c., as per instructions.
	<p>Land, level.</p> <p>Soil, 2nd rate, sandy.</p>
	<p>East on random line between Secs. 1 &amp; 12.</p>
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
80.00	Intersect N. & S. line 81 links North of Section corner.
	<p>N. 89° 25' W. on true line between Secs. 1 &amp; 12.</p>
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
50.00	Leave Umatilla bottom, bears N & S.
80.00	The corner to Secs. 1, 2, 11 & 12.
	<p>Land, level.</p> <p>Soil, 1st rate.</p>
	<p>North on random line between Secs. 1 &amp; 2.</p> <p style="text-align: right;">Variation 20° East.</p>
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
80.15	Intersect North boundary at the corner to Secs. 1 & 2.
	<p>South on true line between Secs. 1 &amp; 2.</p>
40.15	Set post for $\frac{1}{4}$ Sec. corner in mound of earth, as per instructions.
80.15	The corner to Secs. 1, 2, 11 & 12 in mound of earth.