

Subdivisions, T. 3, N., R. 28 E.

Chains

Land, level.
Soil, 2nd rate, very sandy.

North between Secs. 34 & 35.

- 37.50 Trail bears N.E. and S.W.
- 40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
- 80.00 Set post for corner to Secs. 34, 35, 26 & 27 in mound of earth &c., as per instructions.

Land, level.
Soil, 1st rate.

East on random line between Secs. 26 & 35.

- 40.00 Set post for temp. $\frac{1}{4}$ Sec. corner.
- 79.65 Intersect N. & S. line 20 links South of Sec. corner. S. $89^{\circ} 51'$ W. on true line between Secs. 26 & 35.
- 39.83 Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
- 71.65 Trail bears N. E. and S. W.
- 79.65 The corner to Secs. 26, 27, 34 & 35.

Land, level.
Soil, 1st rate.

North between Secs. 26 & 27.

Variation $19^{\circ} 45'$ East.

- 40.00 Set post for $\frac{1}{4}$ Sec. corner in mound of earth, as per instructions.
- 80.00 Set post for corner to Sections 22, 23, 26 & 27 in mound of earth, as per instructions.

Land, level.
Soil, 1st rate.

East on random line between Secs. 23 & 26.

- 40.00 Set post for temp. $\frac{1}{4}$ Sec. corner.