

## Subdivisions, T. 3, N. R. 28 E.

Chains	
	East on random line between Secs. 22 & 27.
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
79.75	Intersect N & S Line 100 links North of Sec. corner. N. $89^{\circ} 17' W.$ on true line between Secs. 22 & 27.
39.88	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
79.75	The corner to Secs. 21, 22, 27 & 28. Land, level. Soil, 2nd rate.
	North between Secs. 21 & 22. Variation $19^{\circ} 30'$ East.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
40.08	Emigrant road to upper crossing of Butter Creek bears SW & NE.
48.25	Emigrant road to lower crossing of butter Creek bears E&W.
80.00	Set post for corner to Secs. 15, 16, 21 & 22 in mound of earth &c., as per instructions. Land, gently rolling. Soil, 2nd rate, sandy.
	East on random line between Secs. 15 & 22.
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
79.75	Intersect N & S line 125 links North of Sec. corner. N. $89^{\circ} 07' W.$ on true line between Secs. 15 & 22.
39.88	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
79.75	The corner to Secs. 15, 16, 21 & 22 in mound of earth. Land, level. Soil, 1st rate, and sandy.
	Sept. 24th, 1859.
	North between Secs. 15 & 16. Variation $20^{\circ}$ East.