

## Subdivisions T. 3, N. R. 28 E.

Chains	
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 9, 10, 15 & 16 in mound of earth &c., as per instructions.
	Land, level.
	Soil, 2nd rate, very sandy.
<hr/>	
	East on a random line between Secs. 10 & 15.
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
79.75	Intersect N. & S. line 120 links North of Sec. corner. N. $89^{\circ} 09'$ W. on true line between Secs. 10 & 15.
39.88	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
79.75	The corner to Secs. 9, 10, 15 & 16. Land, level. Soil, 2nd rate.
<hr/>	
	North between Secs. 9 & 10. Variation $19^{\circ} 55'$ East.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 3, 4, 9 & 10 in mound of earth &c., as per instructions.
	Land, level.
	Soil, 2nd rate.
<hr/>	
	East on random line between Secs. 3 & 10.
40.00	Set post for temp. $\frac{1}{4}$ Sec. corner.
79.66	Intersect N & S Line 140 links North of Sec. corner. N. $89^{\circ}$ W. on true line between Secs. 3 & 10.
39.83	Set post for $\frac{1}{4}$ Sec. corner in mound of earth &c., as per instructions.
79.66	The corner to Secs. 3, 4, 9 & 10. Land, gently rolling. Soil, 2nd rate, very sandy; covered with cactus.