

## Subdivisions T. 3, N. R. 28 E.

Chains	
78.20	Intersect West boundary 50 links South of corner.
10.25	S. 89° 39' East on true line between Secs. 19 & 30.
10.25	Butter Creek 20 links wide runs North.
38.20	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
58.00	Leave bottom bears N & S.
78.20	The corner to Secs. 19, 20, 29 & 30.
	Land, level.
	Soil, 1st rate bottom.
	Sept. 28th, 1859.
<hr/> North between Secs. 19 & 20.	
	Variation 19° 45' East.
36.00	Emigrant Road to Dalles bears E & W.
40.00	Set post for 1/4 Sec. corner in mound of earth.
46.00	Enter bottom bears N. 10° E. & S. 10° W.
80.00	Set post for corner to Secs. 17, 18, 19 & 20, in mound of earth &c., as per instructions.
	Land, level.
	Soil, 1st rate.
<hr/> East on a random line between Secs. 17 & 20.	
40.00	Set post for temp. 1/4 Sec. corner.
80.72	Intersect N & S Line 80 links North of Sec. corner.
	N. 89° 26' W. on true line between Secs. 17 & 20.
20.00	Road bears N.E. & S.W.
40.36	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
70.00	Enter Bottom, bears N.E.
80.72	The corner to Secs. 17, 18, 19 & 20 in mound of earth.
	Land, level.
	Soil, 1st rate.
<hr/> West on random line between Secs. 18 & 19.	
40.00	Set post for temp. 1/4 Sec. corner.