

Field Notes of the Survey of the Exterior  
boundaries of Township 3, N. R. 29 East.  
Survey by N. H. Gates under Contract No. 84.  
Dated July 22, 1859.

Chains	
	From the established corner to Townships 2 and 3 North of Ranges 28 and 29 East, run North between Sections 31 and 36.
40.00	Set post for 1/4 Section corner in earth mound, established as per instructions.
80.00	Set post for corner to Sections 30 and 31, 25 and 36, in mound of earth established as per instructions.
	Land, gently rolling. Soil, good 2nd rate.
	North between Sections 30 and 25. Variation 19° 55' East.
40.00	Set post for 1/4 Section corner in mound of earth, established as per instructions.
80.00	Set post for corner to Sections 19 and 30, 24 and 25, in a mound of earth established as per instructions.
	Land, level. Soil, good 2nd rate. September 12th, 1859.
	North between Sections 19 and 24. Variation 19° 30' East.
23.00	Trail, course E. & W.
40.00	Set post for 1/4 Section corner in earth mound, established as per instructions.
45.25	Immigrant Road, course East and West.
80.00	Set post for Section corner to Secs. 18 and 19, 13 & 24, in mound of earth, established as per instructions.
	Land, level. Soil, 2nd rate.
	North between Sections 18 and 13. Variation 20° 30' East.
40.00	Set post for 1/4 Section corner in mound of earth, established, as per instructions.