

Subdivisions. T. 3 N. R. 29 E.

Chains	
	instructions.
79.45	The corner to Secs. 1, 2, 11 & 12. Land, gently rolling. Soil, 1st rate.
<hr/>	
	North on Random Line between Secs. 1 and 2. Variation 20° 10' East
40.00	Set post for temp. 1/4 Sec. corner.
80.70	Intersect North boundary 56 links East of Sec. corner. S. 24' East on true line between Secs. 1 and 2.
40.70	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.70	The corner to Secs. 1, 2, 11 and 12. Land, gently rolling. Soil, 2nd rate.
<hr/>	
	North between Secs. 34 and 35.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for corner to Secs. 34, 35, 26 & 27 in mound of earth &c., as per instructions. Land, gently rolling. Soil, good 2nd rate.
<hr/>	
	East on random line between Secs. 26 & 35.
40.00	Set post for temp. 1/4 Sec. corner.
80.00	Intersect N. and S. line 46 links South of corner. S. 89° 41' W. on true line between Secs. 26 and 35.
14.00	Emigrant Road bears N.W. & S.E. Enter timber.
36.00	Umatilla River 200 links wide, runs N. 80° West.
40.00	In River.
40.50	Set post for witness to 1/4 Sec. corner, in river 30 links West in mound of earth &c., as per instructions. Leave timber, bears N.W. and S.E.