

Subdivisions of T. 3, N. R. 29 E.

Chains

80.00 The corner to Secs. 26, 27, 34 & 35.
 Land, mostly level.
 Soil, first rate.

North between Secs. 26 & 27.
 Variation 20° 10' East.

13.50 Umatilla River 120 links wide runs N.W.
 15.00 Enter timber and bottom bears N.W. and S.E.
 40.00 Set post for 1/4 Sec. corner, from which
 a Balm 6 in. diam. bears S.15° E. 57 links dist.
 a Balm 8 in. diam. bears S. 45° W. 24 links dist.
 57.00 Leave Bottom bears N.W. and S.E.
 Leave timber bears N.W. and S.E.
 80.00 Set post for corner to Secs. 22, 23, 26 & 27 in mound of
 earth &c., as per instructions.
 Land, level.
 Soil, 1st rate.

East on random line between Secs. 23 & 26.

40.00 Set post for temp. 1/4 Sec. corner.
 79.74 Intersect N. & S. line 22 links South of Sec. corner.
 S. 89° 51' W. on true line between Secs. 23 & 26.
 39.87 Set post for 1/4 Sec. corner in mound of earth &c., as
 per instructions.
 78.50 Emigrant Road bears N.W. & S.E.
 79.74 The corner to Secs. 22, 23, 26 & 27.
 Land, gently rolling.
 Soil, good 2nd rate.

North between Secs. 22 and 23.
 Variation 20° 43' East.

1.20 Emigrant Road bears N.W. and S.E.
 40.00 Set post for 1/4 Sec. corner in mound of earth &c., as
 per instructions.
 80.00 Set post for corner to Secs. 14, 15, 22 & 23 in mound of