

Subdivisions, T. 3, N. R. 29 E.

Chains	
39.20	<p>Set post for witness corner to 1/4 Sec. corner on bank of Umatilla River 68 links West of true corner, from which</p> <p>a Balm 7 in. diameter bears N.12° W., 0.30 links dist.</p> <p>a Balm 8 in. diameter bears S.46° E., .75 links dist.</p> <p>Umatilla River, 200 links wide, runs N.W.</p>
79.76	<p>The corner to Sections 21, 22, 27 and 28.</p> <p>Land, gently rolling.</p> <p>Soil, 1st rate.</p>
<hr/> <p>North between Sections 21 and 22.</p> <p style="text-align: right;">Variation 19° 45' East.</p>	
26.00	<p>Umatilla River runs N. 70° West, 150 links wide.</p> <p>Enter timber.</p>
40.00	<p>Set post for 1/4 Section corner, from which</p> <p>A Balm 13 in. diam. bears S.65° W.35 links dist..</p> <p>A Willow 8 in. diam. bears N. 75° E. 10 links dist.</p>
44.50	<p>Leave timber, bears N. 45° W., S.45° E.</p>
68.75	<p>Emigrant Road to Dalles bears N. 35° W., S. 35° E.</p>
80.00	<p>Set post for corner to Secs. 15,16,21 and 22 in mound of earth &amp;c., as per instructions.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p>
<hr/> <p>East on random line between Sections 15 &amp; 22.</p>	
40.00	<p>Set post for temporary 1/4 Sec. corner.</p>
79.80	<p>Intersect N. &amp; S. line 35 links South of Sec. corner.</p> <p>S. 89° 45' W. on true line between Secs. 15 &amp; 22.</p>
39.90	<p>Set post for 1/4 Sec. corner in mound of earth &amp;c., as per instructions.</p>
75.00	<p>Enter bottom, course bears E. &amp; W.</p>
79.80	<p>The corner to Sections 15,16,21 and 22 in mound of earth.</p> <p>Land, rolling.</p> <p>Soil, good 2nd rate.</p>