

Subdivisions, T. 3, N. R.29 E.

Chains	<p>North between Secs. 28 & 29.</p> <p>Variation 20° 30' East.</p> <p>40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.</p> <p>80.00 Set post for corner to Secs. 20, 21, 28 & 29 in mound of earth &c., as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good 2nd rate.</p>
	<p>East on random line between Secs. 21 and 28.</p> <p>40.00 Set post for temporary 1/4 Sec. corner.</p> <p>80.00 Intersect N. & S. line 81 links South of Sec. corner.</p> <p>S. 89° 25' W. on true line between Secs. 21 & 28.</p> <p>40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.</p> <p>8.00 Leave bottom, course bears N & S.</p> <p>80.00 The corner to Secs. 20, 21, 28 & 29..</p> <p>Land, gently rolling.</p> <p>Soil, 2nd rate.</p> <p>Sept. 20th, 1859.</p>
	<p>North between Secs. 20 & 21.</p> <p>Variation 20° East.</p> <p>40.00 Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.</p> <p>80.00 Set post for corner to Secs. 16, 17, 20 & 21 in mound of earth &c., as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good 2nd rate.</p>
	<p>East on random line between Secs. 16 & 21.</p> <p>40.00 Set post for temporary 1/4 Sec. corner.</p> <p>80.60 Intersect N. & S. line 70 links South of corner.</p> <p>S. 89° 30' W. on true line between Secs. 16 & 21.</p> <p>7.00 Emigrant Road bears N.W. and S.E.</p>