

## Subdivisions, T. 3 N.R. 29 E.

## Chains

20.00 Enter "Sweitzers" Field, course bears N & S.

25.00 Enter timber, course bears N & S.

32.00 Umatilla River, 175 links wide runs N.W.

40.00 In pond of water, set post for witness corner 137 links  
North of true corner from which  
A Balm 5 in. diam. bears N. 25° E. 17 links dist.  
A Willow 4 in. diam. bears S. 1° W. 8 links dist.

60.00 Leave timber, course bears N. & S.

80.60 The corner to Secs. 16, 17, 20 & 21.  
Land, level.  
Soil, 1st rate.

---

North between Secs. 16 & 17.  
Variation 19° 45' East.

7.50 Enter bottom, course bears N.W. & S.E.

36.50 Emigrant Road bears N.W. & S.E.

38.00 House (Old Indian Agency building) bears East about 25.00  
chains distant.

40.00 Set post for 1/4 Sec. corner in mound of earth &c., as  
per instructions.

62.50 Umatilla River runs North 150 links wide.  
Corner to Sections 8, 9, 16 and 17.

80.00 In River set witness post 150 links North of true corner  
in mound of earth &c., as per instructions.  
Land, level.  
Soil, 1st rate.

---

East on a random line between Sections 9 & 16.

40.00 Set post for temporary 1/4 Sec. corner.

80.21 Intersect N. & S. line 70 links South of Sec. corner.  
S. 89° 30' W. on true line between Secs. 9 & 16.

40.10 Set post for 1/4 Sec. corner, in mound of earth &c., as  
per instructions.

53.00 Trail bears North and South.

77.50 Umatilla River, 250 links wide, runs N.W.; offset 150 links