

Subdivisions, T. 3, N. R. 29 E.

Chains	
	North; thence S. 89° 30' W. 271 links to witness post to corner to Secs. 8, 9, 17 and 16.
	Land, gently rolling.
	Soil, good 2nd rate.
	North between Secs. 8 & 9. Variation 20° 10' East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
78.00	Road bears N.W. & S.E.
80.00	Set post for corner to Secs. 4, 5, 8 & 9, in mound of earth &c., as per instructions.
	Land, gently rolling.
	Soil, 1st rate.
	East on random line between Secs. 4 & 9.
40.00	Set post for temporary 1/4 Sec. corner.
79.70	Intersect N. & S. Line 35 links South of Sec. corner. S. 89° 45' West on true line between Secs. 4 & 9.
16.00	Road bears North & South.
39.85	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
79.70	The corner to Secs. 4, 5, 8 & 9. Land, level. Soil, 1st rate.
	North on random line between Secs. 4 & 5. Variation 20° 10' East
40.00	Set post for temporary 1/4 Sec. corner.
80.20	Intersect North boundary 60 links East of Sec. corner. S. 0° 26' East on true line between Secs. 4 & 5.
40.20	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
43.25	Road bears NE and SW.
80.20	The corner to Secs. 4, 5, 8 & 9.