

Subdivisions, T. 3, N. R. 29 E.

Chains	
	North between Sections 29 & 30. Variation 19° 45' East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
80.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
	Land, level.
	Soil, 1st rate.
	Sept. 21st, 1859.
<hr/>	
	East on a random line between Secs. 20 & 29.
40.00	Set post for temporary 1/4 Section corner.
80.50	Intersect N & S Line 38 links South of Sec. corner. S. 89° 44' W. on true line between Secs. 20 & 29.
40.25	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
57.50	Trail bears North & South.
68.40	Trail bears North and South.
80.50	The corner to Secs. 19, 20, 29 & 30. Land, level. Soil, 1st rate.
<hr/>	
	West on a random line between Secs. 19 & 30.
40.00	Set post for temporary 1/4 Sec. corner.
88.70	Intersect West boundary 38 links North of Secs. corner. N. 89° 44' E. on true line between Secs. 19 & 30.
13.60	Trail bears N. 20° W., S. 25° E.
28.20	Trail bears N. 15° E., S. 20° W.
48.70	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
88.70	The corner to Secs. 19, 20, 29 & 30. Land, level. Soil, 1st rate.
<hr/>	