

## Subdivisions, T. 3, N. R. 29 E.

Chains	
	North between Secs. 19 & 20.
	Variation 19° 30' East.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
74.50	Road leading from Agency to Dalles bears N.70°E., S.70° W.
80.00	Set post for corner to Secs. 17, 18, 19 & 20 in mound of earth &c., as per instructions.
	East on a random line between Secs. 17 & 20.
40.00	Set post for temporary 1/4 Sec. corner.
80.45	Intersect N & S Line 77 links South of Sec. corner. S.89° 27' W. on true line between Secs. 17 & 20.
10.45	Trail bears North and East.
19.20	Trail to Butter Creek bears N & S.
40.23	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
71.45	Emigrant Road to Dalles bears N.70° E.
80.45	The corner to Secs. 17, 18, 19 & 20. Land, gently rolling. Soil, 1st rate.
	West on random line between Secs. 18 & 19.
40.00	Set post for temporary 1/4 Sec. corner.
88.29	Intersect West boundary 77 links North of Sec. corner. N. 89° 27' E. on true line between Secs. 18 & 19.
48.29	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.
88.29	The corner to Secs. 17, 18, 19 & 20. Land, level. Soil, 1st rate.
	North between Secs. 17 & 18.
	Variation 19° 30' East.
38.50	Road bears N.10° E., S.20° W.
40.00	Set post for 1/4 Sec. corner in mound of earth &c., as per instructions.