

Subdivisions T.3, N.R. 29 E.

Chains

Land, level.

Soil, rich bottom.

East on a random line between Secs. 5 & 8.

40.00 Set post for temporary 1/4 Sec. corner.

80.80 Intersect N. & S. Line 36 links South of Sec. corner.

S. 89° 45' W. on true line between Secs. 5 & 8.

25.50 Enter River bottom, course bears N. & S.

36.00 Umatilla River, 200 links wide, runs North.

40.40 Set post for 1/4 Sec. corner from which

a Balm 5 in.diameter bears N.70°E.4 links dist.

a Balm 15 in.diameter bears S.16°E.106 lks.dist.

80.80 The corner to Secs. 5, 6, 7 & 8.

Land, level.

Soil, 1st rate.

West on a random line between Secs. 6 & 7.

Variation 20° East.

40.00 Set post for temporary 1/4 Sec. corner.

87.00 Intersect West boundary 38 links North of Sec. corner.

N.89° 44' E. on true line between Secs. 6 & 7.

27.00 Creek, 30 links wide, runs North.

47.00 Set post for 1/4 Sec. corner in mound of earth &c., as
per instructions.

87.00 The corner to Secs. 5, 6, 7 & 8.

Land, level.

Soil, 1st rate.

North on random line between Secs. 5 & 6.

Variation 20° East.

40.00 Set post for temporary 1/4 Sec. corner.

80.00 Intersect North boundary 20 links West of Sec. corner.

S. 08' W. on true line between Secs. 5 & 6.

34.00 Enter timber, course bears N.E. and S.W.

40.00 Set post for 1/4 Sec. corner from which