

Guide Meridian between Ranges 30 & 31 E.
 Surveyed by David P. Thompson, under
 Contract No. 81, dated July 8, 1859.

Chains

13th Mile.

North between Secs. 31 & 36.

Variation 20° 15' East.

28.50 Emigrant Road bears E & W.

40.00 Set post for $\frac{1}{4}$ Sec. corner and build mound of earth with pits, trench &c., as per instructions.

80.00 Set post for corner to Secs. 30, 31, 25 & 36 and build mound of earth with pits, trench &c., as per instructions.

Land, level. Grass, plain.

Soil, 2nd rate.

August 7th, 1859.

14th Mile

North between Secs. 25 & 30.

Variation 20° East.

40.00 Set post for $\frac{1}{4}$ Sec. corner and build mound of earth with pits, trench &c., as per instructions.

80.00 Set post for corner to Secs. 24, 25, 19 & 30 and build a mound of earth with pits, trench &c., as per instructions.

Land, level. Grass, plain.

Soil, 1st rate.

August 7th, 1859.

15th Mile

North between Secs. 19 & 24.

Variation 20° East.

40.00 Set post for $\frac{1}{4}$ Sec. corner and build mound of earth with pits, trench &c., as per instructions.

80.00 Set post for corner to Secs. 18, 19, 13 & 24 and build mound of earth with pits, trench &c., as per instructions.

Land, gently rolling.

Soil, 1st rate.

August 7th, 1857.