

Field Notes of the Exterior  
 Boundaries of T.3 N., R.30 E.  
 Survey made by N. H. Gates, under  
 Contract No. 84, dated July 22, 1859.

West boundary.

Chains	
	<p>From the established corner to Townships 2 and 3, North of Ranges 29 and 30 East, I run North between Secs. 31 and 36.</p>
3.50	Umatilla River; 2 chains wide, course West.
40.00	Set post for $\frac{1}{4}$ Sec. corner in earth mound with charred stake &c., as per instructions.
46.50	Immigrant Road - Course East and West.
80.00	Set post for corner to Secs. 30, 31, 25 & 36 in earth mound, as per instructions.
	Land, rolling.
	Soil, 1st & 2nd rate.
	<hr/> <p>North between Sections 25 and 30.</p>
	Variation 19° 30' East
40.00	Set post for $\frac{1}{4}$ Sec. corner in earth mound with charred stake &c., as per instructions.
80.00	Set post for corner to Secs. 19 & 30, 24 & 25 in earth mound &c., as per instructions.
	Land, gently rolling, grassy hills.
	Soil, good 2nd rate.
	<hr/> <p>North between Sections 19 &amp; 24.</p>
	Variation 20° 30' East
40.00	Set post for $\frac{1}{4}$ Sec. corner in earth mound, established as per instructions.
80.00	Set post for corner to Sections 18 and 19, 13 and 24. Drove charred stake and built mound of earth with trenches, pits &c., in a road, the course of which is E & W.
	Land, gently rolling.
	Soil, 2nd rate.