

N. Bdry. T. 3 N., R. 30 E.

Chains

contains a large amount of good, 2nd rate land, well covered with bunch grass; is suitable for grazing and other purposes and should, therefore, be subdivided.

Field Notes of the Survey of
Subdivisions of T.3 N., R.30 E.
Survey made by Wm. B. Campbell,
Under Contract No. 95,
Dated Sept. 19th, 1860.

North between Sections 35 & 36.

Commence ascent of bluff from post.

24.50 To top of bluff, facing south.

±200

40.00 Set a post for quarter section corner and drove charred stake and raised mound of earth with trench and pits, as per instructions.

43.75 To a wagon road, runs E & W.

80.00 Set a post for corner to Secs. 25 & 26, 35 & 36. Drove a charred stake and raised a mound of earth with trench and pits, as per instructions.

Land on bluff, broken; soil, poor 3rd rate, stony.

Balance land, prairie; soil, good, 2nd rate, providing excellent grass.

East on random between Sections 25 & 36.

Variation 20° 00' E.

40.00 Set temporary quarter section post.

79.97 Intersect Guide Meridian 68 links South of corner to Secs. 25 & 36.

S.89° 31' W. on true line between Secs. 25 & 36.

39.98 Set a post for quarter section corner, drove a charred stake and raised a mound with trench & pits, as per instructions.

79.96 The post for corner to Secs. 25 & 26, 35 & 36.

Land, gently rolling.

Soil, good 2nd rate.