

Subdivisions, T. 3 N., R. 30 E.

Chains	
	North between Secs. 25 & 26.
40.00	Set a post for quarter section corner, drove a charred stake and raised a mound of earth, as per instructions.
80.00	Set a post for corner to Secs. 23, 24, 25 & 26. Drove a charred stake and raised a mound with trench and pits as per instructions.
	Land, gently rolling prairies, nearly level. Soil, good 2nd rate.
<hr/>	
	East on a random line between Sections 24 & 25. Variation 19°45' E.
40.00	Set temporary quarter section post.
79.70	Intersect Guide Meridian 67 <sup>3</sup> / <sub>4</sub> links South of post corner to Secs. 24 & 25. S. 89° 30' W. on a true line between Secs. 24 & 25.
39.85	Set a post for quarter section corner. Drove a charred stake and raised mound of earth, as per instructions.
79.70	The corner to Secs. 23, 24, 25 & 26. Land, gently rolling. Soil, good, 2nd rate.
<hr/>	
	North between Secs. 23 & 24.
40.00	Set a post for quarter section corner and drove a charred stake and raised a mound of earth as per instructions.
80.00	Set a post for corner to Secs. 13, 14, 23 & 24. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.
	Land, nearly level. Soil, good, 2nd rate.
<hr/>	
	East on a random line between Secs. 13 & 24. Variation 19° 45' E.
40.00	Set temporary quarter section post.
80.18	Intersect Guide Meridian at post corner to Secs. 13 & 24.