

## Subdivisions, T. 3 N., R. 30 E.

Chains	
	as per instructions.
80.00	Set a post for corner to Secs. 2, 3, 10 & 11. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.
	Land, rolling prairie.
	Soil, good 2nd rate.
	October 19th, 1860.
<hr/>	
	East on a random line between Sections 2 & 11.
	Variation 20°20' E.
40.00	Set temporary quarter section post.
79.76	Intersect corner to Secs. 1, 2, 11 & 12 at post.
	West, on a true line between Sections 2 & 11.
39.88	Set a post for quarter section corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.
79.76	The post corner to secs. 2, 3, 10 & 11.
	Land, nearly level prairie.
	Soil, good 2nd rate.
<hr/>	
	North on a random line between Sections 2 & 3.
40.00	Set a temporary quarter section post.
82.27	Intersect North boundary of Township, 71 links East of post S.00° 30' E. on a true line between Secs. 2 & 3.
42.27	Set a post for quarter sec. corner. Drove a charred stake and raised mound with trench & pits, as per instructions.
82.27	The post corner to Secs. 2, 3, 10 & 11.
	Land, considerably rolling.
	Soil, good 2nd rate.
<hr/>	
	North between Secs. 33 & 34.
35.16	To Wagon Road, before noted, course NW & SE.
40.00	Set a post for quarter section corner on gentle slope to the North. Drove a charred stake and raised mound with