

Subdivisions, T. 3 N., R. 30 E.

Chains		
	as per instructions.	
80.00	Set a post for corner to Secs. 27, 28, 33 & 34. Snow peak first noted bears N. 57° W. Snow peak second noted bears N. 72° W. Drove a charred stake and raised mound of earth with trench and pits, as per instructions. Land, rolling prairie. Soil, good 2nd rate.	-15
<hr/>		
	East on random line between Sections 27 & 34. Variation 19° 45' E.	
40.00	Set a temporary $\frac{1}{2}$ Section post.	
79.50	Intersect N & S line 9 links North of corner to Secs. 26, 27, 34 & 35. N. 89° 56' W. on a true line between Sections 27 & 34.	
39.75	Set a post for quarter section corner, drove a charred stake and raised mound of earth with trench and pits, as per instructions,	
53.50	To wagon road, course N.W. and S.E.	
79.50	The corner to Secs. 27, 28, 33 & 34. Land, gently rolling with slight descent to the North. Soil, good 2nd rate.	
<hr/>		
	North between Secs. 27 & 28.	
12.60	To wagon road to Umatilla River E & W.	
40.00	Set a post for quarter sec. corner, drove a charred stake and raised a mound of earth, with trench and pits; as per instructions.	
80.00	Set a post for corner to Secs. 21, 22, 27 & 28. Drove a charred stake and raised mound of earth with trench and pits, as per instructions. Snow peak No. 2 bears N. 73° W., from this post. Land, rolling prairie. Soil, good second rate.	