

Subdivisions, T. 3 N., R. 30 E.

Chains		
39.82	Set a post for $\frac{1}{4}$ sec. corner. Drove charred stake & raised mound of earth, with trench & pits, as per instructions.	
52.24	Commence descent.	
54.64	To trail and hollow, foot of descent, N.E.	-150
79.64	The post corner to secs. 4, 5, 8 & 9. Land, considerable rolling prairie. Soil, good 2nd rate.	
<hr/>		
	North on a random line between Secs. 4 and 5. Commence ascent.	
40.00	Set temporary quarter section post.	-150
82.62	Intersect North boundary of Township, 56 links East of post. Corner to Secs. 4 & 5. A rock mound. S.00°24' E. on a true line between Secs. 4 & 5.	+50
2.62	To foot of descent.	-50
12.62	Commence ascending.	
42.62	Set a post for quarter section corner, drove a charred stake and raised a mound of earth, with trench and pits, as per instructions.	+50
66.12	To top of ascent and descend.	+150
82.62	The post corner to sections 4, 5, 8 & 9. Land, considerable rolling prairie. Soil, good 2nd rate.	
<hr/>		
	North, between Secs. 31 & 32 . Ascend from Sec. post.	
25.35	To top of bluff, facing South.	+200
25.35	Indian Trail, course SW & NE.	
30.00	Another trail " " " "	
40.00	Set a post for quarter sec. corner line, drove a charred stake and raised mound with trench and pits, as per instructions.	level
40.70	To a Wagon Road, course SW & NE.	