

Subdivisions, T. 3 N., R. 30 E.

Chains

30.00 Set a post for corner to Secs. 29, 30, 31 & 32. Drove a charred stake and raised mound of earth, with trench and pits, as per instructions.
Land, the 1st 20 chains, 3rd rate prairie; balance, good, 2nd rate, slightly rolling.

East, on random line between Sections 29 & 32.

Variation, 21° 30' E.

40.00 Set a temporary quarter section post.

80.08 Intersect N & S line, 17 links North of corner to Secs. 28, 29, 32 & 32.

N. 89° 53' W. on a true line between Sections 29 & 32.

7.29 To Indian Trail, runs NW & SE.

40.04 Set a post for quarter section corner, drove a charred stake and raised mound of earth with trench and pits, as per instructions.

80.08 The corner to Secs. 29, 30, 31 & 32.

Land, gently rolling prairie.

Soil, good 2nd rate.

West on a random line between Sections 30 & 31.

40.00 Set a temporary quarter sec. post.

level

87.37 Intersect West boundary of Township, 16 links North of post. Corner to Sections 30 & 31.

N. 89° 53' E. on a true line between sections 30 & 31, commence descent.

7.37 To foot of descent.

-25

8.87 To trail SW & NE, commence ascent.

21.87 To top of ascent and commence descent.

+30

26.00 To foot of descent.

-25

32.12 Commence ascent.

45.87 To top of ascent.

+100

47.37 Set post for quarter section corner, drove a charred stake and raised mound of earth, with trench and pits,