

Subdivisions, T. 3 N., R. 30 E.

Chains	
	as per instructions.
87.37	<p>The post corner to secs. 29, 30, 31 and 32. Land, considerably rolling prairie. Soil, good 2nd rate.</p> <p style="text-align: right;">October 23rd, 1860.</p>
40.00	<p>North, between Secs. 29 & 30. Set a post for quarter section corner, drove a charred stake and raised mound of earth with trench and pits, as per instructions.</p>
80.00	<p>Set a post for corner to Secs. 19, 20, 29 & 30. Drove a charred stake and raised mound of earth with trench and pits, as per instructions. Land, rolling prairie. Soil, good, 2nd rate.</p>
40.00	<p>East, on a random line between sections 20 & 29. Variation 20° 00' East.</p>
79.07	<p>Set temporary quarter section post. Intersect N & S line, 26 links North of corner Secs. 20, 21, 28 & 29.</p>
39.53	<p>N. 89° 49' W. on a true line between sections 20 & 29. Set a post for quarter section corner. Drove a charred stake and raised mound of earth with trench and pits, as per instructions.</p>
46.57	<p>To Wagon Road, course N.W. and S.E.</p>
58.07	<p>To a Trail " " " "</p>
79.07	<p>The corner to sections 19, 20, 29 & 30. Land, rolling prairie. Soil, good 2nd rate.</p>
40.00	<p>West on a random line between sections 19 & 30. Set a temporary quarter section post.</p>