

Subdivisions, T. 3 N., R. 30 E.

Chains		
	Soil, good, 2nd rate.	
	West on a random line between Secs. 18 & 19.	
40.00	Set a temporary quarter section post.	
89.61	Intersect West boundary of Township at post, corner to secs. 18 & 19.	
	East on a true line between Secs. 18 & 19.	
	Variation 20° 45' East	
49.61	Set a post for quarter section corner, drove charred stake and raised a mound of earth with trench and pits, as per instructions.	level
64.11	Commence ascending ridge.	
81.61	To top of ascent.	+100
89.61	The post corner to secs. 17, 18, 19 & 20. Land, rolling prairie. Soil, good, 2nd rate.	
	North between Secs. 17 & 18.	
30.00	Commence descending. Trail N.E. & S.W.	
40.00	Set a post for quarter section corner, drove a charred stake and raised a mound of earth with trench and pits, as per instructions.	
72.50	Foot of descent.	-40
80.00	Set a post for corner to Secs. 7, 8, 17 and 18. Drove charred stake and raised a mound of earth, with trench and pits, as per instructions.	level
	Land, rolling prairie.	
	Soil, good 2nd rate.	
	October 25th, 1860.	
	East on a random line between Sections 8 & 17.	
	Variation 20° 15' East.	
40.00	Set a temporary quarter section post.	
79.60	Intersect N & S line, 52 links North of corner to Secs. 8, 9, 16 & 17.	