

North Boundary Township 3 N., R. 31 E. W. M.

Chains	North 89°18' W. on random North line Sec. 2
40.00	Set Temp. $\frac{1}{4}$ sec. post
80.00	Set Temp. post for corner to Secs. 2 & 3, 34 & 35.
	N. 89°18' West on random North line Sec. 3.
40.00	Temp. $\frac{1}{4}$ sec. post
80.00	Temp. corner to Secs. 3 & 4, 33 & 34.
	N. 89°18' W. on random North line of Sec. 4.
40.00	Temp. $\frac{1}{4}$ sec. post
80.00	Temp. corner to Secs. 4 & 5, 32 & 33.
	N. 89°18' W. on random N. line Sec. 5.
40.00	Temp. $\frac{1}{4}$ sec. post
80.00	Temp. corner post to Secs. 5 & 6, 31 & 32.
	N. 89°18' W. on random North line Sec. 6.
40.00	Temp. $\frac{1}{4}$ sec. post.
83.10	Intersect Town line 1.18 chains south of the N. W. corner of Township No. 3 N. and S. W. corner of Township No. 4 N., R. 31 E.
	August 23
	Returning on true line North boundary of Town. No. 3 N., R. 31 E.
	Var. 21°27' E.
	S. 89°09' E. on true North line of section 6, T. 3 N., R. 31 E.
43.10	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
83.10	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 5 & 6, 31 & 32.
	Var. 19°40' E.
	Soil, 3rd rate.
	S. 89°09' E. on true North line Sec. 5
40.00	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. post.