

Subdivision Lines Township No. 3 N., R. 31 E. W. M.

Chains	<p>North on line between Secs. 25 & 26.</p> <p>40.00 Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ section corner.</p> <p>71.00 Dry Ravine (Shallow) course W.</p> <p>80.00 Set charred stake with mound, trench and pits as per insts. for corner to Secs. 23 & 24, 25 & 26.</p> <p style="text-align: right;">Var. 19°21' E.</p> <p>Land, rolling.</p> <p>Soil, 2nd rate.</p>
	<p>S. 89°18' E. on random between Secs. 24 & 25.</p> <p>40.00 Set Temp. qr. sec. post.</p> <p>80.12 Intersect Town line 15 lks. South of corner to Secs. 24 & 25.</p> <p>N. 89°24' W. on true line between Secs. 24 & 25.</p> <p>40.06 Set charred stake with mound, trench and pits as per insts. for qr. sec. corner.</p> <p>77.50 Small ravine S. 80° W.</p> <p>80.12 Corner to Secs. 23 & 24, 25 & 26.</p> <p>Soil, good.</p>
	<p>North on line between Secs 23 & 24.</p> <p>40.00 Set charred stake with mound, trench and pits as per insts. for qr. sec. corner.</p> <p>80.00 Set charred stake with mound, trench and pits as per insts. for corner to Secs. 13 & 14, 23 & 24.</p> <p style="text-align: right;">Var. 20°06' E.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p>
	<p>S. 89°18' E. on random between Sections 24 & 13.</p> <p>40.00 Set Temp. qr. sec. post.</p> <p>80.22 Intersect Town line 55 lks. North of corner to Secs. 13 & 24.</p> <p>N. 88°54' W. on true line between Secs. 13 & 24.</p> <p>40.11 Set charred stake with mound, trench and pits as per</p>