

Subdivision Lines Township No. 3 N., R. 31 E. W. M.

Chains 80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 22 & 23, 26 & 27. Var. 19°30' E. Soil, 2nd rate.
40.00	S. 89°18' E. on random between Secs. 23 & 26. Temp. $\frac{1}{4}$ sec. post.
80.07	Intersect section line 32 links North of corner to Secs. 23, 24, 25 & 26. N. 89°05' W. on true line between Secs. 23 & 26.
40.03	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. post.
65.07	Ravine N. 50° W.
80.07	Corner to Secs. 22, 23, 26 & 27. Soil, 2nd rate.
	August 27
	North on line between Secs. 22 & 23.
13.25	Ravine N. 50° W.
40.00	Set charred stake with mound, trench and pits as per insts. for qr. sec. corner.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 14, 15, 22 & 23. Var. 19°50' E.
40.00	S. 89°18' E. on random between Secs. 14 & 23. Set Temp. $\frac{1}{4}$ sec. post.
79.70	Intersect section line at corner to Sections 13, 14, 23 & 24. N. 89°18' W. on true line between Secs. 14 & 23.
39.85	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
79.70	Corner to Secs. 14, 15, 22 & 23. Soil, 2nd rate.
40.00	North on true line between Secs. 14 & 15. Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. post.
80.00	Set charred stake with mound, trench & pits as per