

Subdivision Lines Township 3 N., R. 31 E. W. M.

Chains	<p>North on line between Secs. 8 & 9.</p> <p>40.00 Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.</p> <p>80.00 Set charred stake with mound trench and pits as per insts. for corner to Secs. 4 & 5, 8 & 9. Var. 21°15' E.</p> <p>Soil, 2nd rate.</p>
	<p>S. 89°18' E. on random between Secs. 4 & 9.</p> <p>40.00 Set Temp. $\frac{1}{4}$ sec. post.</p> <p>80.30 Intersect sec. line 65 lks. North of corner to Secs. 3 & 4, 9 & 10. N. 88°50' W. on true line between Secs. 4 & 9.</p> <p>40.15 Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.</p> <p>80.30 Corner to Secs. 4 & 5, 8 & 9. Soil, 2nd rate.</p>
	<p>North on random between Secs. 4 & 5.</p> <p>40.00 Set Temp. $\frac{1}{4}$ sec. post.</p> <p>79.40 Intersect Town. line 50 lks. West of corner to Secs. 4 & 5. S. 21' W. on true line between Secs. 4 & 5.</p> <p>39.40 Set charred stake with mound, trench and pits as per Instrs. for $\frac{1}{4}$ sec. corner</p> <p>64.00 Ravine N. 50° W.</p> <p>79.40 Corner to Secs. 4 & 5, 8 & 9. Soil, 2nd rate.</p>
	<p>August 30</p> <p>North on line between Secs. 31 & 32. Var. 19°36' E.</p> <p>8.50 Road to Walla Walla (E. & W.)</p> <p>40.00 Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ section corner.</p> <p>80.00 Set charred stake with mound, trench and pits as per insts. for corner to Secs. 29, 30, 31 & 32.</p>