

Subdivision Lines Township 3 N., R. 31 E. W. M.

Chains	
40.00	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
80.00	Set charred stake with mound, trench and pits as per insts. for corner to Secs. 5, 6, 7 & 8. Var. 19°20' E. Soil, 2nd rate.
	S. 89°18' E. on random between Secs. 5 & 8.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
79.28	Intersect sec. line 55 links South of corner to Secs. 4 & 5, 8 & 9. N. 89°42' W. on true line between Secs. 5 & 8.
39.64	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
79.28	Corner to Secs. 5, 6, 7 & 8. Soil, 2nd rate.
	North on random line between Secs. 5 & 6.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
79.75	Intersect Town. line 23 links West of corner to Secs. 5 & 6. S. 10' W. on true line between Secs. 5 & 6.
39.75	Set charred stake with mound, trench & pits as per insts. for $\frac{1}{4}$ sec. corner.
79.75	Corner to Secs. 5, 6, 7, & 8. Soil, 2nd rate.
	N. 89°18' W. on random between Secs. 6 & 7.
40.00	Set Temp. $\frac{1}{4}$ sec. post.
82.87	Intersect Town line 48 lks. North of corner to Secs. 6, 7. S. 89°39' E. on true line between Secs. 6 & 7.
27.00	Ravine N. 25° W.
42.87	Set charred stake with mound, trench and pits as per insts. for $\frac{1}{4}$ sec. corner.
82.87	Corner to Secs. 5, 6, 7, 8. Soil sandy, 2nd rate.