

Exterior Boundaries of Township 3 N., Range No. 32 E.W.M.

<p>Chains 80.00</p>	<p style="text-align: center;">East Boundary</p> <p>Set post for corner to Secs. 12, 13, 7 & 18 in mound of Earth with charred stake, pits, trench, &c as per instructions.</p> <p>Land, level.</p> <p>Soil, 1st rate.</p>
<p>40.00 80.00</p>	<p>North on East boundary of Sec 12.</p> <p style="text-align: center;">Variation 20° E.</p> <p>Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits, trench, &c as per instructions.</p> <p>Set post for corner to Secs. 6, 7, 1 & 12 in mound of Earth with charred stake, pits, trench, &c as per instructions.</p> <p>Land, gently rolling.</p> <p>Soil, good 2nd rate.</p>
<p>40.00 80.00</p>	<p>North on East boundary of Sec. 1.</p> <p style="text-align: center;">Var. 20° East</p> <p>Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits, trench, &c as per instructions.</p> <p>Set post for corner to Townships 3 & 4 North, Ranges 32 & 33 East in mound of Earth with charred stake, pits, trench, &c as per instructions.</p> <p>Land, gently rolling</p> <p>Soil, 1st rate.</p>
	<p>Exterior Boundaries of Township 3, North of Range 32, East Willamette Meridian.</p> <p style="text-align: center;">North Boundary</p> <p>West on a random line between Townships 3 & 4, North Range 32 East.</p> <p>I set temporary half mile and mile posts at 40.00 and 80.00 chains.</p> <p>I find the line to be 6 miles 3 chains and 12 links and the falling to be 164 lks. north of Township corner. The correction for the true line will therefore be $27\frac{1}{3}$ lks. per mile North.</p> <p>From the corner to Townships 3 & 4. North,</p>