

Subdivision Lines of Township 3 North, Range 32 E. W. M.

Chains	
78.00	Umatilla & Walla Walla Road bears N.E. & S. W.
80.20	The corner to Secs. 23, 24, 25 & 26. Land, level. Soil, 1st rate.
	North between Secs. 23 & 24. Var. $19\frac{1}{2}^{\circ}$ East.
40.00	Set post for $\frac{1}{4}$ Sec. corner in mound of Earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 13, 14, 23 & 24 in mound of Earth with charred stake, pits &c as per instructions. Land, rolling. Soil, good 3rd rate.
	East on a random line between Secs. 13 & 24.
40.00	Set post for temporary $\frac{1}{4}$ Sec. cor.
80.39	Intersect East boundary 54 lks. South of corner to Secs. 13 & 24 from which I run S. $89^{\circ}37'$ W. on a true line between Secs. 13 & 24.
40.20	Set post for $\frac{1}{4}$ Sec. cor in mound of Earth with charred stake, pits &c as per instructions.
80.39	The corner to Secs. 13, 14, 23 & 24. Land, level. Soil, 1st rate.
	North between Secs. 13 & 14. Var. 20° E.
40.00	Set post for $\frac{1}{4}$ Sec. cor. in mound of Earth with charred stake, pits &c as per instructions.
80.00	Set post for corner to Secs. 11, 12, 13 & 14 in mound of Earth with charred stake, pits &c as per instructions. Land, gently rolling. Soil, 1st rate.
	East on a random line between Secs. 12 & 13.
40.00	Set post for temporary $\frac{1}{4}$ Sec. corner.